

SCHEDULE - A

Name of Work : HT Electrification System at KCA Cricket Ground, Mangalapuram						
Supply & Commissioning of Ring Main Unit (RMU)						
Sl No	Description of Item	Unit	Qty	Rate	Amount (INR)	Remarks
1	RING MAIN UNIT – Supply and commissioning of dust and vermin proof, floor mounted, free standing cubicle type, communicable type 11kV Metal Enclosed Outdoor Extensible at one end, Compact Ring Main Unit made out of robotically welded stainless steel tank of IP67 class of protection fully compartmentalized complete with hinged and earthed front doors interlocked with the earth switch. The switch-gear should have the minimum degree of protection (in accordance with IEC 60529) - RMUs of CTT/CVV Configuration - IP 67 for the tank with high voltage components - IP 54 for the front covers of the mechanism - IP54 for the cable connection covers	Each	1			
	Make : Schneider					
	Incomer - 11kV, 630A, 350 MVA, Motor operated, Compact, Outdoor, LBS with earth switch - 2 Set Outgoings - 11kV, 630A, 350 MVA, Motor operated, Compact, Outdoor, Non draw out type VCB with O/C & EF self powered Relays + TP Disconnecter, etc. CVC configuration. Rate shall be inclusive of pre-commissioning test with all accessories and requirements for successful pre-commissioning of unit, as instructed by engineer in charge/consultant and in accordance with all relevant standards and requirements.	Set	1			
	Total Cost in Rs.					

- Rate should be inclusive of freight charges for delivery at KCA Cricket Ground, Mangalapuram, Trivandrum
- GST should be shown separately.

Signature
Name of the Company