

SCHEDULE - A

Name of Work : HT Electrification System at KCA Cricket Ground, Mangalapuram						
Supply & Commissioning of 200KVA 11KV/433 V Transformer						
Sl No	Description of Item	Unit	Qty	Rate	Amount (INR)	Remarks
1	<p>TRANSFORMER - Supply & commissioning of 200 kVA 11kV/433V outdoor cast resin dry type ,(Copper Double Wound) having a continuous rating for 11kV / 433V 3 phase 50 Hz. Vector group Dyn 11 with tapping +5% to -10% in steps of 2.5 % by tap links, include winding temperature indicator. Transformer should have cable end box on HV side suitable for 3Cx300 sq.mm XLPE cable and LV side suitable for 1RX3.5CX300 sq.mm A2XFY cable, with all accessories, complete as required as per State electricity board, ECBC, IE rules specifications. The transformer shall confirm to IS 2067/77, 11171/1985 with latest amendment etc complete. Foundation for TXR shall be done by other agency.</p>	Each	1			
	Make: KEL / Resitech / ABB / Megawin / Unitech / Unipower / Intrans/					
	Total Cost in Rs.					

- Rate should be inclusive of freight charges for delivery at KCA Cricket Ground, Mangalapuram, Trivandrum
- GST should be shown separately.

Signature
Name of the Company