

KERALA CRICKET ASSOCIATION

Tender Schedule : Supply and Installation of Rootzone layer and Grass at Mini Cricket Ground, KCA-SD College Ground, Alappuzha

SI No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
1	630	m3	Providing and installing root zone, over graded and rolled subgrade include necessary trimming to form the required camber and gradients with layers of course graded medium, fine graded sand to a minimum thickness and providing sand manure mix layer consisting of medirmr fine sand , biofibre and biosoil @10kg/sq.mtr to a minimum thickness of 100mm.Mixing the above to ensure a homogenous mix and accurate mix of componerrts. The sand rrumure mix shall be compacted repeatedly by rolling to the grade; camber required and irrigating as required. The cost shall include applyrng pre mergence herbicide, pre plant fertilizers @ 10kg/sqm to the entire are4 cost of all labour, material lead, stacking of sand atsite etc complete as directed by the Engineer in charge.		/m3		
2	6300	m2	Supply and planting the paspalum grass over the sand bed closely to get a thick grass lawn suitable for ground in rows in both direction, keep the area moisture by spraying and sprinkling water till the grass gets sufficient deep roots cutting to level the top surface, trimming and dressing etc. complete as directed by the engineer in charge		/m2		
			Total				
			GST				
			Total (Incl of GST)				

Sign & Seal of Contractor

Address:

Place :

Date: