

KERALA CRICKET ASSOCIATION

GARDEN LAND SCAPING, NATURAL STONE PAVING AND ALLIED WORKS AT MANGALAPURAM CRICKET STADIUM, THIRUVANANTHAPURAM

Tender Schedule

Sl. No.	Quantity		Description	Rate in figures	Unit	Rate in Words	Amount
1	1463.00	m2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.		/m2		
2	15741.88	sqft	Providing and laying Pearl grass carpet in the soft land scape area including preparation of the yard, levelling in required slope, labour charges for trimming, dressing and watering as required until the grass properly takeout root and continue for a period of not less than three month, including cost and conveyance of pearl grass planting charges, watering mowing to the required slope and shape and direction of the Agronomist.		/sqft		
3	4795.36	sqft	Providing and laying with 100 x 100 x 100 mm hard granite cobblestones after neatly dressing and consolidating the sub grade and over a layer of 5 cm thick 6 mm hard garinte broken stone at a spacking of 25 mm to 30 mm as directed by the Architect, filling the gap with pearl grass/buffallow grass including cost of allmaterials, labour charges etc complete.		/sqft		
4	136.36	m2	Providing and laying with 600 x300 x 50 mm hard granite natural stones (Departmental stone) after neatly dressing and consolidating the sub grade and over a layer of 5 cm thick 6 mm hard garinte broken stone at a spacking of 40 mm to 50 mm as directed by the Architect, filling the gap with pearl grass/buffallow grass including cost of allmaterials, labour charges etc complete.		/m2		
5	400.00	m2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge;		/m2		

Sl. No.	Quantity		Description	Rate in figures	Unit	Rate in Words	Amount
6	4.00	no	Providing and planting Plumeria dort, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
7	24.00	no	Providing and planting Heliconia, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
8	3.00	no	Providing and planting Terminalia green tree, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
9	5.00	no	Providing and planting Ribbon grass brown, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
10	28.00	no	Providing and planting Eugenia plant, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
11	10.00	no	Providing and planting Bottle brush, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
12	14.00	no	Providing and planting Spider lily, including preparation of the bed, watering and manuring as required until the grass properly takeout root and continue for a period of not less than three month, direction of the Agronomist.		/no		
13	4.00	bags	Supply of fertilizer for trees and plants, including cost of all materials, conveyance,unloading charges etc complete.		/bags		

Sl. No.	Quantity		Description	Rate in figures	Unit	Rate in Words	Amount
14	9.45	cum	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).		/cum		
15	4.40	sqm	Providing and laying 80mm thick factory made cement concrete interlocking paver block of M-40grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand ,fillingthe joints with line sand etc. all complete as per the direction of Engineer in charge				
			Total				
			Add GST 18%				
			Add for rounding				
			Grand total				
<p>Note : The contractor will perform monthly maintenance for the landscaping, covering lawns, trees, shrubs, hedges, flowerbeds, and other elements. This includes tasks such as watering, weeding, mowing, pruning, trimming, fertilizing, pest control, removing dead leaves and debris, and ensuring the overall health and appearance of the area. All work will adhere to standard horticultural practices to maintain a neat and tidy landscape throughout the year. These services are to be included in the rates specified.</p>							

Rupees (in words) :

Place:

Seal & Sign :

Date:

**Name & Address of
Contractor :**

KERALA CRICKET ASSOCIATION

**GARDEN LAND SCAPING, NATURAL STONE PAVING AND ALLIED WORKS AT
MANGALAPURAM CRICKET STADIUM, THIRUVANANTHAPURAM**

GENERAL APPROVED MAKE OF MATERIALS		
Sl no	Item	Approved Make/ Size
	<i>Civil</i>	
1	Cobble stone	100x100mm
2	Kerbstone	M25 grade,150mm Thick
3	Paver Blocks	M40 Grade,80x80cm
4	Natural stone	120x30cm
5	Steel reinforcement	Tata steel/ Jindal/ JSW/ Tulsyan or Equivalent
6	Cement -OPC 33 grade	Ultratech/Ambuja/ACC/JSW or Equivalent
7	Granite stones	Jet black
8	Built up tubular sections- GI	Tata steel/Jindal
	<i>Landscape</i>	
1	Spider lilly	
2	Heliconia	
3	Bottle brush tree	
4	Grass	
5	Ribbon grass	
6	Terminalia tree	
7	Plumeria tree	
8	Euginia	
	<i>Locations</i>	
1	Amphitheatre area	
2	Landscape area- near to Amphitheatre	
3	Utilitiy Block area	
4	Parking area	

Note : Selection of materials subject to approval from the KCA officials

Sign and Seal of Contractor