

KERALA CRICKET ASSOCIATION

Fabrication of 9m height Ball Hit Fence at KCA Cricket Ground, SD College Alappuzha

Tender Schedule

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
1	25.66	m3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m and lift upto 1.5m.		/m3		
2	2.85	m3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)		/m3		
3	90.11	m2	Centering and shuttering including strutting, propping etc. and removal of form for all heights -Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.		/m2		
4	18.02	m3	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)		/m3		
5	2972.97	kg	Steel reinforcement for R.C.C. work including straightening, cutting, bending,placing in position and binding all complete upto plinth level - Thermo-Mechanically Treated bars of grade Fe-500D or more.		/kg		

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
6	5.28	m3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.		/m3		
7	12588.71	kg	Frame work in built up tubular (round, square or rectangular 16 gauge hollow GI tubes etc.) including cutting, hoisting, fixing position and applying a priming coat of approved metal primer, including welding and bolted with special shaped washers etc. complete. (Hot finished welded type tubes)		/kg		
8	4439.98	m2	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. on steel works		/m2		
9	2320.00	m2	Providing and fixing 40 mm square pattern 3.mm braided HDPE nets tying with 3 mm toins, fixing in GI Builtup frames already fixed including accessories such as 3.5mm GI rope at top and bottom, clamp, cost of all other materials, labour charges etc. complete.		/m2		
10	2000.00	kg	Supply and fixing of GI foundation plate and anchor bolts		/kg		
			Total				
			GST				
			Total (Incl of GST)				

Rupees in Words:

Sign & Seal of Contractor

Place :

Name & Address:

Date: