

KERALA CRICKET ASSOCIATION

Fabrication of Compound Fencing Works at KCA Twin Cricket Ground, Thodupuzha

Tender Schedule

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
1	1779.05	m2	Providing and fixing G.I. welded mesh fencing of required width in mesh size 50x50 mm made of G.I. wire of dia 4 mm complete as per the direction of Engineer-in-charge.		/m2		
2	15678.18	kg	Steel work in GI built up tubular (round, square or rectangular hollow tubes etc.)trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished welded type tubes		/kg		
3	3030.66	m2	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works.		/m2		
4	1966.36	kg	Supply and fixing 200x200mm GI foundation plate 8mm thickness and 8mm anchor bolts		/kg		
			Total				
			GST				
			Total (Incl of GST)				

Rupees in Words:

Sign & Seal of Contractor

Place :

Name & Address:

Date: